

**TOWN OF BRASELTON  
VINEYARDS LIFT STATION REPLACEMENT PROJECT  
DECEMBER 20, 2018**

ITEM NO.	DESCRIPTION	UNIT	Est. No. of Units	Griffin Bros, Inc.		Allsouth Constructors, Inc.		IHC Construction Companies, Inc.		
				UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM	
				103 Griffin Drive Maysville, GA 30558 706-677-3549		9124 North Park Dr. Covington, GA 30014 770-788-8703		1500 Executive Dr. (2700 Delk Rd., SE, Suite 210) Elgin, IL 60123 (Marietta, GA 30067) 404-497-7619		
02227.00	ROCK REMOVAL - TRENCH ROCK	CY	200	\$70.00	\$14,000.00	\$70.00	\$14,000.00	\$70.00	\$14,000.00	
02270.00	EROSION CONTROL									
02270.01	SILT FENCE - TYPE C	LF	500	\$2.50	\$1,250.00	\$2.50	\$1,250.00	\$2.25	\$1,125.00	
02270.02	CONSTRUCTION EXIT	EA	1	\$1,627.68	\$1,627.68	\$500.00	\$500.00	\$1,630.00	\$1,630.00	
02601.00	MANHOLES									
02601.01	STANDARD 4'-0" MANHOLE INCLUDES BASE, CONE, RISER, FRAME AND COVER, COMPLETE, 0'-6' DEPTH	EA	2	\$3,138.55	\$6,277.10	\$1,500.00	\$3,000.00	\$4,500.00	\$9,000.00	
02601.02	4'-0" CUT-IN MANHOLE INCLUDES BASE, CONE, RISER, FRAME AND COVER, COMPLETE, 0'-6' DEPTH	EA	2	\$4,215.41	\$8,430.82	\$2,000.00	\$4,000.00	\$4,500.00	\$9,000.00	
02601.03	4'-0" MANHOLE ADDITIONAL VERTICAL FEET	VF	19	\$170.00	\$3,230.00	\$100.00	\$1,900.00	\$415.00	\$7,885.00	
02601.04	EXISTING MANHOLE ABANDONMENT	EA	1	\$1,000.00	\$1,000.00	\$500.00	\$500.00	\$2,800.00	\$2,800.00	
02601.05	EXISTING STORAGE BASIN ABANDONMENT	EA	1	\$1,500.00	\$1,500.00	\$1,000.00	\$1,000.00	\$3,000.00	\$3,000.00	
02602.00	EXISTING MANHOLE COATINGS									
02602.01	COATING EXISTING FM DISCHARGE 4'-0" DIAMETER MANHOLE	VF	6	\$223.69	\$1,342.14	\$1,250.00	\$7,500.00	\$1,250.00	\$7,500.00	
02603.00	NEW MANHOLE/WETWELL COATINGS									
02603.01	COATING NEW 10'-0" DIAMETER WETWELLS	VF	16	\$543.80	\$8,700.80	\$1,125.00	\$18,000.00	\$1,100.00	\$17,600.00	
02603.02	COATING NEW 4'-0" DIAMETER MANHOLES	VF	14	\$223.69	\$3,131.66	\$470.00	\$6,580.00	\$565.00	\$7,910.00	
02732.00	SANITARY SEWER FORCEMAINS									
02732.01	6" DIA. DR 18 C900 PVC FORCEMAIN	LF	70	\$138.93	\$9,725.10	\$20.00	\$1,400.00	\$85.00	\$5,950.00	
02732.02	6" DIA. PLUG VALVE - COMPLETE WITH VALVE BOX	EA	3	\$2,449.07	\$7,347.21	\$2,000.00	\$6,000.00	\$1,800.00	\$5,400.00	
02736.00	SANITARY SEWER									
02736.01	8" DIA. SDR 35 PVC, ALL DEPTHS	LF	195	\$126.48	\$24,663.60	\$40.00	\$7,800.00	\$100.00	\$19,500.00	
02931.01	PERMANENT GRASSING	LS	1	\$3,000.00	\$3,000.00	\$1,500.00	\$1,500.00	\$3,000.00	\$3,000.00	
11310.00	SUBMERSIBLE SEWAGE PUMP STATION									
11310.01	VINEYARDS LIFT STATION - COMPLETE, INCLUDING DUPLEX SUBMERSIBLE SEWAGE PUMP STATION, SITE WORK, FENCING, PIPING, WATER SERVICE, VALVES, VAULTS, WETWELL, ODOR CONTROL SYSTEM, GENERATOR, ALL ELECTRICAL WORK, CONCRETE, SCADA, ACCESS ROAD, AND ANY RELATED MATERIALS	LS	1	\$462,032.84	\$462,032.84	\$637,000.00	\$637,000.00	\$745,700.00	\$745,700.00	
11310.02	EXISTING LIFT STATION ABANDONMENT, COMPLETE	LS	1	\$15,000.00	\$15,000.00	\$5,000.00	\$5,000.00	\$12,000.00	\$12,000.00	
<b>TOTAL AMOUNT BASE BID</b>						\$572,258.95		\$716,930.00		\$873,000.00

I hereby certify this to be a true and accurate tabulation of bids received by the Town of Braselton, Georgia on December 20, 2018.

Greg Bennett, PE  
Engineering Management, Inc.

