

**REED CREEK PHASE II
WATER IMPROVEMENTS PROJECT TARGET AREA II-COKESBURY HIGHWAY
HART COUNTY WATER AND SEWER AUTHORITY**

ITEM NO.	DESCRIPTION	UNIT	Est. No. of Units	Dale Construction Company P.O. Box 789/791 Doster Rd. Jefferson, GA 30549 706-215-4380		Arrowood General Contracting, Inc. P.O. Box 459 Eastanollee, GA 30538 706-491-4546	
				UNIT PRICE	TOTAL FOR ITEM	UNIT PRICE	TOTAL FOR ITEM
00520.00	PERFORMANCE BOND	LS	1	\$1,000.00	\$1,000.00	\$2,400.00	\$2,400.00
00530.00	LABOR & MATERIAL PAYMENT BOND	LS	1	\$1,000.00	\$1,000.00	\$5,000.00	\$5,000.00
00700.00	INSURANCE	LS	1	\$1,000.00	\$1,000.00	\$3,000.00	\$3,000.00
01025.00	VIDEO TAPING THE WATERLINE ROUTE (CD/DVD FORMAT)	LS	1	\$500.00	\$500.00	\$500.00	\$500.00
02227.00	ROCK REMOVAL-TRENCH ROCK	CY	100	\$70.00	\$7,000.00	\$70.00	\$7,000.00
02270.00	EROSION CONTROL						
02270.01	SILT FENCE-TYPE A	LF	5,795	\$0.10	\$579.50	\$0.10	\$579.50
02270.02	HAYBALE CHECK DAMS	EA	79	\$0.10	\$7.90	\$20.00	\$1,580.00
02300.00	BORING AND JACKING						
02300.01	JACK & BORE CONVENTIONAL-COMPLETE WITH 16" DIA. STEEL CASING AND 8" DIA. CLASS 350 DUCTILE IRON WATER CARRIER PIPE, SPACERS, END SEALS, ETC.	LF	190	\$155.00	\$29,450.00	\$155.00	\$29,450.00
02300.02	ADD ON CHARGE-BORING AND JACKING THROUGH ROCK-COMPLETE WITH 16" DIA. STEEL CASING AND 8" DIA. CLASS 350 DUCTILE IRON WATER CARRIER PIPE, SPACERS, END SEALS, ETC.	LF	50	\$1.00	\$50.00	\$5.00	\$250.00
02300.03	8" FREEBORE-COMPLETE, INCLUDING 8" DIP, ETC.	LF	60	\$55.00	\$3,300.00	\$50.00	\$3,000.00
02300.04	8" FREEBORE-COMPLETE, INCLUDING 8" PVC DR 18 C900 PIPE, ETC.	LF	80	\$40.00	\$3,200.00	\$40.00	\$3,200.00
02523.00	SIDEWALKS, DRIVEWAYS, CURBS AND GUTTERS						
02523.01	GRAVEL DRIVEWAY RESTORATION PER DETAIL GP8 ON SHEET D3 OF THE PLANS	LF	207	\$8.00	\$1,656.00	\$8.00	\$1,656.00
02645.00	FIRE HYDRANTS ASSEMBLIES						
02645.01	FIRE HYDRANT ASSEMBLY-COMPLETE	EA	10	\$3,000.00	\$30,000.00	\$3,000.00	\$30,000.00
02645.02	8" LINE TERMINATIONS WITH FIRE HYDRANT ASSEMBLY-COMPLETE	EA	1	\$3,500.00	\$3,500.00	\$3,100.00	\$3,100.00
02660.00	WATER DISTRIBUTION SYSTEMS						
02660.01	8" DIA. AWWA C900 PVC DR 18 WATER PIPE, INCLUDES FITTINGS, RESTRAINT, ETC.	LF	10,867	\$12.50	\$135,837.50	\$13.50	\$146,704.50
02660.02	8" GATE VALVE-COMPLETE INCLUDING VALVE BOX, CONCRETE PAD, MARKER, ETC.	EA	5	\$1,200.00	\$6,000.00	\$1,200.00	\$6,000.00
02660.03	CONNECT PROPOSED WATERLINE TO EXISTING 8" GATE VALVE.	EA	1	\$750.00	\$750.00	\$500.00	\$500.00
02660.04	8" RESTRAINED JOINTS	EA	20	\$1.00	\$20.00	\$5.00	\$100.00
02665.00	WATER SERVICE CONNECTIONS						
02665.01	3/4" SHORT SIDE SERVICE CONNECTIONS-COMPLETE; (OWNER TO PROVIDE METER AND METER BOX. CONTRACTOR TO INSTALL)	EA	20	\$450.00	\$9,000.00	\$450.00	\$9,000.00
02665.02	3/4" LONG SIDE SERVICE CONNECTIONS-COMPLETE; (OWNER TO PROVIDE METER AND METER BOX. CONTRACTOR TO INSTALL)	EA	20	\$500.00	\$10,000.00	\$600.00	\$12,000.00
02931.00	MULCH WITH PERMANENT GRASSING	LF	10,660	\$0.95	\$10,127.00	\$1.00	\$10,660.00
TOTAL BASE BID					\$253,977.90		\$275,680.00

**REED CREEK PHASE II
WATER IMPROVEMENTS PROJECT TARGET AREA II-COKESBURY HIGHWAY
HART COUNTY WATER AND SEWER AUTHORITY**

MANDATORY ALTERNATE BID ITEMS

ITEM NO.	DESCRIPTION	UNIT	Est. No. of Units	Dale Construction Company P.O. Box 789/791 Doster Rd. Jefferson, GA 30549 706-215-4380		Arrowood General Contracting, Inc. P.O. Box 459 Eastanollee, GA 30538 706-491-4546	
				PRICE	FOR ITEM	PRICE	FOR ITEM
APPENDIX A	NPDES PLAN IMPLEMENTATION	LS	1	\$1,500.00	\$1,500.00	\$2,000.00	\$2,000.00
Total Bid Including Alternates					\$255,477.90	\$277,680.00	

**TOTAL BID FOR THE REED CREEK PHASE II WATER IMPROVEMENTS PROJECT
TARGET AREA II-COKESBURY HWY:**

I hereby certify this to be a true and accurate tabulation
of bids received by the Hart County Water and Sewer Authority
on September 19, 2017.

Zack Bryan, PE
Engineering Management, Inc.

